

AD-A106 313

PRC CONSOER TOWNSEND INC ST LOUIS MO  
NATIONAL DAM SAFETY PROGRAM. BRANNEY LAKE DAM (MO 31393), MISS--ETC(U)  
MAY 81 W G SHIFRIN DACW43-80-C-0094

F/6 13/13

ML

UNCLASSIFIED

for 1  
2000-3-18

END

DATE

FILED

11-81

NTIC

**LEVEL** 1-0

**MISSOURI - KANSAS CITY RIVER BASIN**

AD A106313

BRANNEKY LAKE DAM  
ST. LOUIS COUNTY, MISSOURI  
MO. 31393

**PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM**



**United States Army  
Corps of Engineers**

*Serving the Army  
Serving the Nation*

**St. Louis District**

This document has been approved  
for public release and sale; its  
distribution is unlimited.

PREPARED BY: U. S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR: STATE OF MISSOURI

MAY 1981



A

81 10 26 064

ENC. COPY

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A106	313
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Branneky Lake Dam (MO 31393) St. Louis County, Missouri		5. TYPE OF REPORT & PERIOD COVERED Final Report
6. AUTHOR(s) Consoer, Townsend and Associates, Ltd.		7. PERFORMING ORG. REPORT NUMBER
8. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		9. CONTRACT OR GRANT NUMBER(s) DACW43-80-C-0094
10. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		11. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
12. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) (6) National Dam Safety Program, Branneky Lake Dam (MO 31393), Missouri - Kansas City River Basin, St. Louis County, Missouri. Phase I Inspection Report.		13. REPORT DATE May 1981
14. DATE		15. NUMBER OF PAGES Approximately 80
16. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) Approved for release; distribution unlimited.		17. SECURITY CLASS. (of this report) UNCLASSIFIED
18. SUPPLEMENTARY NOTES		19. DECLASSIFICATION/DOWNGRADING SCHEDULE
20. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
21. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.		


DD FORM 1 JAN 70 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

## INSTRUCTIONS FOR PREPARATION OF REPORT DOCUMENTATION PAGE

**RESPONSIBILITY.** The controlling DoD office will be responsible for completion of the Report Documentation Page, DD Form 1473, in all technical reports prepared by or for DoD organizations.

**CLASSIFICATION.** Since this Report Documentation Page, DD Form 1473, is used in preparing announcements, bibliographies, and data banks, it should be unclassified if possible. If a classification is required, identify the classified items on the page by the appropriate symbol.

### COMPLETION GUIDE

**General.** Make Blocks 1, 4, 5, 6, 7, 11, 13, 15, and 16 agree with the corresponding information on the report cover. Leave Blocks 2 and 3 blank.

**Block 1.** Report Number. Enter the unique alphanumeric report number shown on the cover.

**Block 2.** Government Accession No. Leave Blank. This space is for use by the Defense Documentation Center.

**Block 3.** Recipient's Catalog Number. Leave blank. This space is for the use of the report recipient to assist in future retrieval of the document.

**Block 4.** Title and Subtitle. Enter the title in all capital letters exactly as it appears on the publication. Titles should be unclassified whenever possible. Write out the English equivalent for Greek letters and mathematical symbols in the title (see "Abstracting Scientific and Technical Reports of Defense-sponsored RDT/E," AD-667 000). If the report has a subtitle, this subtitle should follow the main title, be separated by a comma or semicolon if appropriate, and be initially capitalized. If a publication has a title in a foreign language, translate the title into English and follow the English translation with the title in the original language. Make every effort to simplify the title before publication.

**Block 5.** Type of Report and Period Covered. Indicate here whether report is interim, final, etc., and, if applicable, inclusive dates of period covered, such as the life of a contract covered in a final contractor report.

**Block 6.** Performing Organization Report Number. Only numbers other than the official report number shown in Block 1, such as series numbers for in-house reports or a contractor/grantee number assigned by him, will be placed in this space. If no such numbers are used, leave this space blank.

**Block 7.** Author(s). Include corresponding information from the report cover. Give the name(s) of the author(s) in conventional order (for example, John R. Doe or, if author prefers, J. Robert Doe). In addition, list the affiliation of an author if it differs from that of the performing organization.

**Block 8.** Contract or Grant Number(s). For a contractor or grantee report, enter the complete contract or grant number(s) under which the work reported was accomplished. Leave blank in in-house reports.

**Block 9.** Performing Organization Name and Address. For in-house reports enter the name and address, including office symbol, of the performing activity. For contractor or grantee reports enter the name and address of the contractor or grantee who prepared the report and identify the appropriate corporate division, school, laboratory, etc., of the author. List city, state, and ZIP Code.

**Block 10.** Program Element, Project, Task Area, and Work Unit Numbers. Enter here the number code from the applicable Department of Defense form, such as the DD Form 1498, "Research and Technology Work Unit Summary" or the DD Form 1634, "Research and Development Planning Summary," which identifies the program element, project, task area, and work unit or equivalent under which the work was authorized.

**Block 11.** Controlling Office Name and Address. Enter the full, official name and address, including office symbol, of the controlling office. (Equates to funding/sponsoring agency. For definition see DoD Directive 5200.20, "Distribution Statements on Technical Documents.")

**Block 12.** Report Date. Enter here the day, month, and year or month and year as shown on the cover.

**Block 13.** Number of Pages. Enter the total number of pages.

**Block 14.** Monitoring Agency Name and Address (if different from Controlling Office). For use when the controlling or funding office does not directly administer a project, contract, or grant, but delegates the administrative responsibility to another organization.

**Blocks 15 & 15a.** Security Classification of the Report: Declassification/Downgrading Schedule of the Report. Enter in 15 the highest classification of the report. If appropriate, enter in 15a the declassification/downgrading schedule of the report, using the abbreviations for declassification/downgrading schedules listed in paragraph 4-207 of DoD 5200.1-R.


**Block 16.** Distribution Statement of the Report. Insert here the applicable distribution statement of the report from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

**Block 17.** Distribution Statement (of the abstract entered in Block 20, if different from the distribution statement of the report). Insert here the applicable distribution statement of the abstract from DoD Directive 5200.20, "Distribution Statements on Technical Documents."

**Block 18.** Supplementary Notes. Enter information not included elsewhere but useful, such as: Prepared in cooperation with . . . Translation of (or by) . . . Presented at conference of . . . To be published in . . .

**Block 19.** Key Words. Select terms or short phrases that identify the principal subjects covered in the report, and are sufficiently specific and precise to be used as index entries for cataloging, conforming to standard terminology. The DoD "Thesaurus of Engineering and Scientific Terms" (TEST), AD-672 000, can be helpful.

**Block 20.** Abstract. The abstract should be a brief (not to exceed 200 words) factual summary of the most significant information contained in the report. If possible, the abstract of a classified report should be unclassified and the abstract to an unclassified report should consist of publicly-releasable information. If the report contains a significant bibliography or literature survey, mention it here. For information on preparing abstracts see "Abstracting Scientific and Technical Reports of Defense-Sponsored RDT&E," AD-667 000.



**DEPARTMENT OF THE ARMY**  
**ST. LOUIS DISTRICT, CORPS OF ENGINEERS**  
**210 TUCKER BOULEVARD, NORTH**  
**ST. LOUIS, MISSOURI 63101**

REPLY TO  
ATTENTION OF

**SUBJECT: Branneky Lake Dam (Mo. 31393) Phase I Inspection Report**

This report presents the results of field inspection and evaluation of the Branneky Lake Dam (Mo. 31393).

It was prepared under the National Program of Inspection of Non-Federal Dams.

This dam has been classified as unsafe, emergency by the St. Louis District as a result of the application of the following criteria:

- 1) The spillway will not pass a 10-year frequency flood without overtopping of the dam. The spillway is, therefore, considered to be unusually small and seriously inadequate.
- 2) Overtopping of the dam could result in dam failure.
- 3) Dam failure significantly increases the hazard to loss of life downstream.

SUBMITTED BY: \_\_\_\_\_

**SIGNED**  
Chief, Engineering Division

**8 JUN 1981**

\_\_\_\_\_  
Date

APPROVED BY: \_\_\_\_\_

**SIGNED**  
Colonel, CE, District Engineer

**11 JUN 1981**

\_\_\_\_\_  
Date

A

BRANNEY LAKE DAM  
ST. LOUIS COUNTY, MISSOURI

MISSOURI INVENTORY NO. 31393

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

PREPARED BY  
PRC CONSOER TOWNSEND, INC.  
ST. LOUIS, MISSOURI  
AND  
PRC ENGINEERING CONSULTANTS, INC.  
ENGLEWOOD, COLORADO  
A JOINT VENTURE

UNDER DIRECTION OF  
ST. LOUIS DISTRICT, CORPS OF ENGINEERS  
FOR  
GOVERNOR OF MISSOURI

MAY 1981

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

Name of Dam:           Branneky Lake Dam,  
                          Missouri Inventory No. 31393  
  
State Located:        Missouri  
County Located:      St. Louis  
Stream:                Unnamed tributary of the Missouri River  
Date of Inspection: March 3, 1981

Assessment of General Condition

Branneky Lake Dam was inspected by the engineering firms of PRC Consoer Townsend, Inc. of St. Louis, Missouri, and PRC Engineering Consultants, Inc. of Englewood, Colorado (A Joint Venture) in accordance with the U. S. Army Corps of Engineers "Recommended Guidelines for Safety Inspection of Dams" and additional guidelines furnished by the St. Louis District of the Corps of Engineers. Based upon the criteria in the guidelines, the dam is in the high hazard potential classification, which means that loss of life and appreciable property loss could occur in the event of failure of the dam. Located within the estimated damage zone of one mile downstream of the dam are four dwellings, one building, and an interstate highway, which may be subjected to flooding, with possible damage and/or destruction, and possible loss of life. Branneky Lake Dam is in the small size classification since it is 33.6 feet high and impounds 46 acre-feet of water.


The inspection and evaluation of the consultant's inspection team indicate that the spillway of Branneky Lake Dam does not meet the criteria set forth in the guidelines for a dam having the above size and




hazard potential. Branneky Lake Dam being a small size dam with a high hazard potential is required by the guidelines to pass from one-half of the Probable Maximum Flood to the Probable Maximum Flood without overtopping the dam. Considering the small drainage area, the small storage capacity of the reservoir, the height of the dam, and the small number of dwellings in the downstream hazard zone, one-half of the Probable Maximum Flood is considered the appropriate spillway design flood for Branneky Lake Dam. The Probable Maximum Flood is defined as the flood discharge that may be expected from the most severe combination of critical meteorological and hydrologic conditions that are reasonably possible in the region. It was determined that the reservoir can store approximately 5 percent of the Probable Maximum Flood without overtopping the dam. The evaluation also indicates that the reservoir cannot accommodate the ten-percent chance flood without overtopping the the dam.

The overall condition of the dam appears to be fair; however, the severe obstruction of the corrugated metal pipe in the spillway jeopardizes the safety of the dam. Other deficiencies, noted by the inspection team, included: an area of standing water observed at the toe of the dam indicating possible seepage through the embankment; obstructions in the approach and discharge channels of the spillway; the erosion due to wave action, trees and animal burrows observed on the upstream slope; a need exists for periodic inspection by a qualified engineer; and there also exists a lack of maintenance and a maintenance schedule. The lack of seepage and stability analyses on record is also a deficiency that should be corrected.

It is recommended that the owner take action to correct or control the deficiencies described above.

  
Walter G. Shifrin, P.E.





Overview of Branneky Lake Dam

NATIONAL DAM SAFETY PROGRAM

BRANNEKY LAKE DAM, I.D. No. 31393

TABLE OF CONTENTS

<u>Sect. No.</u>	<u>Title</u>	<u>Page</u>
SECTION 1	PROJECT INFORMATION . . . . .	1
	1.1 General . . . . .	1
	1.2 Description of Project . . . . .	2
	1.3 Pertinent Data . . . . .	6
SECTION 2	ENGINEERING DATA . . . . .	9
	2.1 Design . . . . .	9
	2.2 Construction . . . . .	9
	2.3 Operation . . . . .	9
	2.4 Evaluation . . . . .	9
SECTION 3	VISUAL INSPECTION . . . . .	11
	3.1 Findings . . . . .	11
	3.2 Evaluation . . . . .	17

## TABLE OF CONTENTS

(Continued)

<u>Sect. No.</u>	<u>Title</u>	<u>Page</u>
SECTION 4	OPERATION PROCEDURES . . . . .	19
	4.1 Procedures . . . . .	19
	4.2 Maintenance of Dam . . . . .	19
	4.3 Maintenance of Operating Facilities . . . . .	19
	4.4 Description of Any Warning System in Effect . . . . .	19
	4.5 Evaluation . . . . .	20
SECTION 5	HYDRAULIC/HYDROLOGIC . . . . .	21
	5.1 Evaluation of Features . . . . .	21
SECTION 6	STRUCTURAL STABILITY. . . . .	24
	6.1 Evaluation of Structural Stability. . . . .	24
SECTION 7	ASSESSMENT/REMEDIAL MEASURES. . . . .	26
	7.1 Dam Assessment . . . . .	26
	7.2 Remedial Measures. . . . .	28

## TABLE OF CONTENTS

(Continued)

### LIST OF PLATES

	<u>Plate No.</u>
LOCATION MAP . . . . .	1
DRAINAGE BASIN AND DOWNSTREAM HAZARD ZONE. . . . .	2
PLAN AND ELEVATION OF THE DAM. . . . .	3
SPILLWAY PROFILE AND MAXIMUM SECTION . . . . .	4
GEOLOGIC MAPS . . . . .	5-7
SEISMIC ZONE MAP . . . . .	8

### APPENDICES

APPENDIX A        -        PHOTOGRAPHS

APPENDIX B        -        HYDROLOGIC AND HYDRAULIC COMPUTATIONS

PHASE I INSPECTION REPORT  
NATIONAL DAM SAFETY PROGRAM

BRANNEKY LAKE DAM, Missouri Inv. No. 31393

SECTION 1: PROJECT INFORMATION

1.1 General

a. Authority

The Dam Inspection Act, Public Law 92-367 of August, 1972, authorizes the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspections. Inspection for Branneky Lake Dam was carried out under Contract DACW 43-80-C-0094 between the Department of the Army, St. Louis District, Corps of Engineers, and the engineering firms of PRC Consoer Townsend, Inc., of St. Louis, Missouri and PRC Engineering Consultants, Inc., of Englewood, Colorado (A Joint Venture).

b. Purpose of Inspection

The visual inspection of Branneky Lake Dam was made on March 3, 1981. The purpose of the inspection was to make a general assessment as to the structural integrity and operational adequacy of the dam embankment and its appurtenant structures.

c. Scope of Report

This report summarizes available pertinent data relating to the project, presents a summary of visual observations made during the field inspection, presents an assessment of hydrologic and hydraulic conditions at the site, and of the structural adequacy

of the various project features and assesses the general condition of the dam with respect to safety.

Subsurface investigations, laboratory testing and detailed analyses were not within the scope of this study. No warranty as to the absolute safety of the project features is implied by the conclusions presented in this report.

It should be noted that in this report reference to left or right abutments is viewed as looking downstream. Where left abutment or left side of the dam is used in this report, this also refers to the northwest abutment or side, and right to the southeast abutment or side.

d. Evaluation Criteria

The inspection and evaluation of the dam is performed in accordance with the U.S. Army Corps of Engineers "Recommended Guidelines for Safety Inspection of Dams" and additional guidelines furnished by the St. Louis District office of the Corps of Engineers for Phase I Dam Inspection.

1.2 Description of the Project

a. Description of Dam and Appurtenances

The following description is based upon observations and measurements made during the visual inspection and conversations with Mr. Henry Branneky, the original owner of the dam. No design or "as-built" drawings for the dam or appurtenant structures were available.

The dam is a homogeneous, rolled, earthfill structure, according to Mr. Branneky. The alignment of the dam is straight between earth abutments. A plan and elevation of the dam are shown on Plate 3 and Photos 1 through 3 show views of the dam. The dam

has a length of 440 feet and an assumed minimum top of dam elevation of 508 feet above mean sea level (M.S.L.). The top of dam was surveyed to be level between two points 100 feet and 140 feet from the right and left abutments, respectively. From the point 100 feet to the left of the right abutment, the top of dam slopes upward to the end of the dam with a rise in elevation of 1.3 feet. From the point 140 feet to the right of the left abutment, the top of dam slopes upward to the abutment contact with a rise in elevation of 1.1 feet. The embankment has a top width of 46 feet and a downstream slope of 1 vertical to 3.75 horizontal (1V to 3.75H). The upstream slope was measured to be near vertical for the first two feet below the top of dam and then 1V to 6H to the water surface on the day of the inspection. The maximum structural height of the dam was measured to be 33.6 feet.

The only spillway at this damsite consists of grasslined approach and discharge channels cut into the right abutment and a 24-inch diameter, corrugated metal pipe, control section. At the inlet of the approach channel is a welded wire screen one foot high and four feet long supported by a wooden frame (see Photo 5). The approach channel leads to the corrugated metal pipe (CMP) which passes under the road that extends across the top of the dam (see Photo 6). The CMP discharges into the discharge channel that extends approximately 100 feet downstream from the axis of the dam to where it enters the apparent downstream channel (see Photo 9). The spillway lies in a direction almost perpendicular to the axis of the dam. The earthcut channels are trapezoidal in shape with an average bottom width of ten feet and 1V to 2.5H side slopes. The spillway crest elevation was measured to be at 506.5 feet above M.S.L.

No low-level outlet or outlet works were provided for this dam.



b. Location

Branneky Lake Dam is located in St. Louis County in the State of Missouri on an unnamed tributary of the Missouri River. The dam is located approximately 0.6 mile to the northwest of the intersection of Interstates 70 and 270 and 3 miles southeast of St. Charles, Missouri, in Survey No. 282, Township 46 North, Range 5 East as shown on the St. Charles and Creve Coeur, Missouri Quad-range (7.5 minute series) sheets. The axis of the dam is situated parallel to and approximately 900 feet southwest of Interstate 70.

c. Size Classification

The maximum structural height of the dam is less than 40 feet and greater than 25 feet, which classifies it as a "small" size dam. The maximum reservoir impoundment of Branneky Lake Dam is less than 50 acre-feet, which is the minimum storage requirement for a structure to be classified as a dam. Nevertheless, the size classification is determined by either the storage or height, whichever gives the larger size category. Therefore, the size classification is determined to fall within the "small" category, according to the "Recommended Guidelines for Safety Inspection of Dams" by the U.S. Department of the Army, Office of the Chief Engineer.

d. Hazard Classification

The dam has been classified as having a "high" hazard potential in the National Inventory of Dams, on the basis that in the event of failure of the dam, excessive damage could occur to downstream property, together with the possibility of the loss of life. From a visual inspection of the downstream area, our findings concur with this classification. Located within the estimated damage zone, which extends approximately one mile downstream of the dam, are four dwellings, one building (Boise-Cascade Plant) and an interstate highway (I-70) (see Photos 11 and 12).

e. Ownership

A property line divides Branneky Lake Dam into two property parcels. According to a recent survey by Fred Weber, Inc., approximately one-third of the dam is owned by Fred Weber, Inc. and the western two-thirds of the dam is owned by the Pillsbury Foundation. The mailing addresses are as follows: Fred Weber, Inc., c/o Mr. Bill Powell, 7929 Alabama Avenue, St. Louis, Missouri, 63111 and Pillsbury Foundation, c/o Mr. J.S. Pillsbury, #6 Oakleigh Lane, St. Louis, Missouri, 63124.

f. Purpose of Dam

According to Mr. Ken Kaiser of Fred Weber, Inc., the dam was built to store water for use in fighting potential fires at the Boise-Cascade Plant, located just downstream of the dam.

g. Design and Construction History

Mr. Henry Branneky, the previous owner of Branneky Lake Dam, said that the dam was built about 12 to 15 years ago by Bangert Brothers Construction Company of St. Louis, Missouri. The Bangert Brothers Construction Company was developing an industrial site just downstream of the dam at the time the dam was built. Mr. Branneky was also not aware of any drawings or specifications for the dam. It is unknown who did the actual engineering design of the dam.

h. Normal Operational Procedures

Normal procedure at the Branneky Lake Dam is to allow the reservoir to remain as full as possible. The water level is controlled by rainfall, runoff, evaporation, and the elevation of the spillway crest.

1.3      Pertinent Data

a.    Drainage Area (square miles): . . . 0.14

b.    Discharge at Damsite

Estimated experienced maximum flood (cfs): . . . . . Unknown

Estimated ungated spillway capacity with  
reservoir at top of dam elevation (cfs): . . . . . 1.5

c.    Elevation (Feet above MSL)

Top of dam: . . . . . 508.0 (assumed)\*

Spillway crest: . . . . . 506.5

Normal Pool: . . . . . 505.5 (Evidence of  
Past Water Level)

Maximum Experienced Pool: . . . . . Unknown

Observed Pool: . . . . . 503.4

d.    Reservoir

Length of pool with water surface  
at top of dam elevation (feet): . . . . . 1200

e.    Storage (Acre-Feet)

Top of dam: . . . . . 46

Spillway crest: . . . . . 34

Normal Pool: . . . . . 28

Maximum Experienced Pool: . . . . . Unknown

Observed Pool: . . . . . 19

f.    Reservoir Surfaces (Acres)

Top of dam: . . . . . 8.5

Spillway crest: . . . . . 7.0

Normal Pool: . . . . . 6.5

Maximum Experienced Pool: . . . . . Unknown

Observed Pool: . . . . . 5.0

g. Dam

Type: . . . . . Rolled, Earthfill  
Length: . . . . . 440 feet  
Structural Height: . . . . . 33.6 feet  
Hydraulic Height\*\*: . . . . . 33.6 feet  
Top width: . . . . . 46 feet  
Side slopes:  
    Downstream . . . . . 1V to 3.75H  
    Upstream . . . . . Varies, near vertical  
                                for the top two feet  
                                and 1V to 6H to the  
                                water surface.  
Zoning: . . . . . N.A., Homogeneous  
Impervious core: . . . . . None  
Cutoff: . . . . . None  
Grout curtain: . . . . . Unknown  
Volume: . . . . . 58,100 cu. yds.  
                                (Estimated)

h. Diversion and Regulating Tunnel . . . None

i. Spillway

Type: . . . . . Earthcut channel with  
                                a 24-inch diameter  
                                corrugated metal pipe as  
                                the control section.  
Length of crest: . . . . . N.A.  
Crest Elevation (feet above MSL): . . . . . 506.5

j. Regulating Outlets . . . . . None

\* No exact elevation is known for the top of dam, therefore, an elevation was estimated from the St. Charles, Missouri, U.S.G.S. Quadrangle sheet. This estimated elevation is referred to as assumed elevation.

All other elevations were determined from the assumed top of dam elevation and field measurements.

\*\* The hydraulic height of the dam is the vertical distance from the lowest point on the downstream toe to the top of dam or the maximum water surface, if below the top of dam.

## SECTION 2: ENGINEERING DATA

### 2.1 Design

No design drawings, "as-built" drawings or calculations were available for Branneky Lake Dam.

### 2.2 Construction

No data are available concerning the construction of the dam and appurtenant structures. The following information about the construction of the dam was obtained from conversations with Mr. Henry Branneky. The dam was built using a dragline and bulldozers. The dragline removed the embankment material from the lakebed and placed it on the fill. The activity of the bulldozers across the fill compacted the embankment material. No compaction control was employed and no cutoff trench was excavated for the embankment.

### 2.3 Operation

No operational records for this dam were available to the inspection team.

### 2.4 Evaluation

#### a. Availability

The availability of engineering data is poor and consists only of State Geological Maps, a general soil map of the State of Missouri published by the Soil Conservation Service, and U.S.G.S. Quadrangle Sheets.

b. Adequacy

The conclusions presented in this report are based on field measurements, the available engineering data, past performance and present condition of the dam. The available data, including the field measurements taken by the field inspection team, are considered adequate to evaluate the hydraulic and hydrologic capabilities of the dam. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.

c. Validity

No valid engineering data pertaining to the design or construction of the dam were available.

### SECTION 3: VISUAL INSPECTION

#### 3.1 Findings

##### a. General

A visual inspection of the Branneky Lake Dam was made on March 3, 1981. The following persons were present during the inspection:

<u>Name</u>	<u>Affiliation</u>	<u>Disciplines</u>
Mark Haynes, P.E.	PRC Engineering Consultants, Inc.	Soils
Jerry Kenny	PRC Engineering Consultants, Inc.	Hydraulics and Hydrology
James Nettum, P.E.	PRC Engineering Consultants, Inc.	Civil-Structural and Mechanical
Razi Quraishi, R.P.G.	PRC Engineering Consultants, Inc.	Geology
John Lauth, P.E.	PRC Consoer Townsend, Inc.	Civil-Structural
Marc Ramsey	Representative of Fred Weber, Inc.	
Ken Kaiser	Representative of Fred Weber, Inc.	

Specific observations are discussed below.



b. Dam

The overall condition of the dam appeared to be fair, however, some items of concern were observed and are described below.

The top of dam is occasionally used as an access road and consequently, some minor tire rutting was observed (see Photo 2). On either side of the road, the top of dam is adequately protected from surface erosion by a good grass cover. No depressions or cracking indicative of an instability of the embankment were apparent. The variation in the elevation at both ends of the dam did not appear to be due to an instability of the embankment or foundation. No significant deviation in the horizontal alignment was apparent. There was no evidence of the dam ever being overtopped.

The upstream slope has no riprap protection. Consequently, considerable wave erosion of the slope above the apparent normal water surface level has occurred. The slope has been steepened to near vertical above the normal water surface level (see Photo 4) and in a few areas, the wave erosion has extended into the top of dam. Undercutting of the slope was also observed in several areas, which indicates future sloughing of the slope is possible. The portion of the slope above the wave erosion was protected against surface runoff erosion by an adequate cover of grass (see Photo 4). No bulges, depressions or cracks indicative of any movement of the embankment or foundation were apparent. Several medium sized trees were growing on the slope.

The downstream slope is adequately protected against surface runoff by a good grass cover and no erosional problems due to surface runoff were observed. No bulges, depressions or cracks indicative of an instability of the slope were apparent. An area of trees and standing water approximately 90 feet long and located about 135 feet to the left of the right abutment was observed at the

toe of the dam. It was undetermined whether the source of the water was due to seepage through the embankment or foundation or was due to surface runoff which has collected in the area, since the area has no means of being drained. No measurable flow of seepage was observed in the above mentioned area, on the embankment or downstream of the toe. No trees were growing on the downstream slope.

The right abutment slopes gently upward from the dam and the left abutment is at approximately the same elevation as the top of dam. No instabilities, seepage or erosion which were felt to be detrimental to the safety of the dam were observed on either abutment. However, one erosion gully was observed on the left abutment but it was felt that the gully does not affect the safety of the dam in its present condition nor will it affect the dam in the future if further erosion occurs.

Animal burrows measuring up to 4 inches in diameter were observed on the upstream slope. However, no evidence of burrowing animals was apparent on either the downstream slope or either abutment.

#### c. Project Geology and Soils

##### (1) Project Geology

The damsite is located on an unnamed tributary of the Missouri River in the Springfield Plateau section of the Ozark Plateaus Physiographic Province. The Springfield Plateau includes that part of the Ozarks which is underlain mainly by rocks of Mississippian age. Most of the Springfield Plateau are prairies, which are separated by valleys cut 200 to 300 feet below the upland surface. Most of the area of the Springfield Plateau is overlain by a mantle of chert derived by weathering of the Mississippian Limestone. Widespread distribution of dolomite and limestone bedrock with deep dissection is responsible for the development of many springs in the regional area of the damsite. A major component

of the surface discharge of water to the regional drainage is contributed by these springs.

Topography at the damsite vicinity is rolling to hilly with V-shaped valleys. Elevations of the ground surface range from 637 feet above M.S.L. approximately 2.9 miles northeast of the damsite to 515 feet above M.S.L. at the damsite. The reservoir slopes are generally from 6 degrees to 12 degrees from horizontal. The reservoir slopes are stable and the reservoir appears to be watertight. The area near the damsite is covered with loess deposits consisting of brownish gray, slightly plastic clayey silt, trace fine sand.

The regional bedrock geology beneath the loess deposits in the damsite area as shown on the Geologic Map of Missouri (1979), (see Plate 5) consist of Pennsylvanian age rocks of the Pleasanton-Marmaton-Cherokee Group and Mississippian St. Louis Formation. The predominant bedrock underlying the loess deposits in the vicinity of the damsite are the Pennsylvanian age rocks of Pleasanton-Marmaton Group (cyclic deposits of shale, limestone and sandstone). No outcropping of bedrock was seen at the damsite.

No faults have been identified in the vicinity of the damsite. The closest trace of a fault to the damsite is the St. Louis fault nearly 14 miles east of the damsite. The St. Louis fault had its last movement in Paleozoic time. Thus, the fault has no effect on the damsite.

No boring logs or construction reports were available that would indicate foundation conditions encountered during the construction. Based on the visual inspection the embankment rests on loess deposits. The approach and discharge channels of the spillway were cut into the loessial soils of the right abutment. The corrugated metal pipe located at the control section of the spillway rests on the loessial soils.

## (2) Project Soils

According to Mr. Ramsey, the soil overburden in the reservoir area is of the Knox soil group with soil deposits up to 40 feet to the underlying bedrock at the damsite. The Knox soil type, as classified by the Soil Conservation Service, is a loess deposited silty clay loam.

Materials removed from the embankment on the upstream and downstream slopes approximately 1 foot below the vegetative cover ranged from a brown, clayey silt with a trace of fine sand to a brown, slightly plastic, silty clay with a trace of fine sand. Based upon the Unified Soil Classification System, the soil would probably be classified as an ML-CL. This soil type generally has the following characteristics; impervious with a coefficient of permeability less than 1.0 foot per year, medium to low shear strength, and an intermediate resistance to piping.

### d. Appurtenant Structures

#### (1) Spillway

The spillway channels are lined with a dense cover of long grass. Numerous trees up to 6 inches in diameter are growing along the entire length (see Photo 9). The channels are stable as no erosion was seen. The control section for the spillway is the 24-inch diameter CMP under the road which extends across the dam. The pipe is silted up to within 0.7 foot at the inlet and 0.4 foot at the outlet, therefore the capacity of the pipe is considerably reduced from its original condition (see Photo 7). The wire screen and its wooden frame supports across the inlet of the spillway also appears to hinder the proper operation of the spillway.

## (2) Outlet Works

No low level outlet or outlet works were provided for this dam.

### e. Reservoir Area

The reservoir water surface elevation at the time of the inspection was 503.4 feet above M.S.L. The normal water surface level for the reservoir is unknown; however, due to physical evidence observed on the upstream slope and along the reservoir rim, the normal water surface level elevation was assumed to be at 505.5, which is one foot below the spillway crest. The surface area of the reservoir at the apparent normal water level is about 6.5 acres.

The rim appeared to be stable with no major erosional problems observed. The land around the reservoir slopes gently upward from the rim and is primarily used for agricultural purposes (see Photo 10). One house is built upstream of the reservoir. No evidence of excessive siltation was observed in the reservoir on the day of the inspection.

### f. Downstream Channel

The downstream channel near the dam is undefined and obstructed with trees and bushes. Discharges from the spillway flow along the right abutment until they reach a 30-inch diameter CMP that leads into a concrete lined basin. The concrete lined basin collects water from several sources and directs it into a 8 feet wide by 6.25 feet high box culvert which passes under the interstate highway.

### 3.2 Evaluation

The severe obstruction of the spillway pipe due to the siltation is cause for alarm. The siltation severely reduces the capacity of the spillway, which could cause the dam to be overtopped during large flows thus endangering the safety of the dam.

The following conditions were also observed, which could adversely affect the dam in the near future.

1. The area of standing water at the toe of the dam could affect the structural stability of the dam, however, it was undetermined if the condition was due to seepage or if surface runoff collected in the area and was unable to drain off. If the standing water was indeed due to seepage and the rate of seepage were to increase, it is possible that the seepage could transport soil particles. This could cause piping of embankment material which could lead to an eventual failure of the embankment. No flowing seepage was observed in the area on the day of the inspection.

2. The trees and brush in the spillway channels and the wire screen and its supports across the inlet of the spillway also reduce the capacity of the spillway, but does not appear to have caused any damage to the dam at this time. However, flows of an appreciable size could easily cause overtopping of the dam, which could seriously affect the stability of the embankment.

3. The trees observed on the upstream slope pose a potential danger to the safety of the dam depending upon the extent of the root system. The roots of large trees present possible paths for piping through the embankment. The root systems can also do damage to the embankment from being uprooted by a storm.

4. The animal activity observed on the upstream slope could jeopardize the safety of the dam. The holes created by the small animals make avenues for possible piping.

5. The wave erosion on the upstream slope does not appear to affect the stability of the dam in its present condition, due to the fact that the top of dam is fairly wide and the freeboard height above the apparent normal water surface is only 2.5 feet. However, continual erosion of the slope can only be detrimental to the stability of the dam.

## SECTION 4: OPERATIONAL PROCEDURES

### 4.1 Procedures

There are no specific procedures which are followed for the operation of Branneky Lake Dam. The water level below the spillway crest is allowed to remain as high as possible.

### 4.2 Maintenance of Dam

Fred Weber, Inc. purchased a part of the dam that includes the spillway channel from Gould, Inc. of Rollings Meadows, Illinois several months ago. It appears that the dam and the spillway have been neglected and have received little or no maintenance. The spillway channels have overgrown with brush and trees. The 24-inch diameter spillway pipe has almost completely filled up with silt. The upstream dam slope has been eroded by wave action and several medium sized trees are growing on the upstream slope of the dam.

### 4.3 Maintenance of Operating Facilities

There are no operating facilities associated with Branneky Lake Dam.

### 4.4 Description of Any Warning System in Effect

The inspection team is not aware of any existing warning system in effect for the dam, such as an electrical warning system or a manual notification plan.



#### 4.5      Evaluation

The dam appears to be neglected and the maintenance for Branneky Lake Dam seems to be inadequate at this time. The remedial measures outlined in Section 7 should be undertaken to improve the condition of the dam.

## SECTION 5: HYDRAULIC/HYDROLOGIC

### 5.1 Evaluation of Features

#### a. Design Data

No hydrologic and hydraulic design data are available for Branneky Lake Dam. The sizes of physical features utilized to develop the stage-outflow relation for the overtopping of the dam were prepared from field notes and sketches prepared during the field inspection. The reservoir elevation-area data were based on the U.S.G.S. St. Charles and Creve Coeur, Missouri Quadrangle topographic maps (7.5 minute series). The overtop release rates and the reservoir elevation-area data are presented in Appendix B.

The hydrologic soil group of the watershed was determined from information available in the U.S.D.A. Soil Conservation Service publication "Missouri General Soil Map and Soil Association Descriptions", 1979. The Probable Maximum Precipitation (PMP) used to determine the Probable Maximum Flood (PMF) was determined by using the U.S. Weather Bureau publication "Hydrometeorological Report No. 33" (April 1956). The 100-year and the 10-year floods were derived from the 100-year rainfall and the 10-year rainfall, respectively, of St. Louis, Missouri.

#### b. Experience Data

It is believed that records of reservoir stage or spillway discharge are not maintained for this site. However, there was no evidence of the dam ever having been overtopped.

c. Visual Observations

Observations made of the spillway during the visual inspection are discussed in Section 3.1d and evaluated in Section 3.2.

d. Overtopping Potential

Both the Probable Maximum Flood and one-half of the Probable Maximum Flood, when routed through the reservoir, resulted in overtopping of the dam. The peak inflows of the PMF and one-half of the PMF are 1,918 cfs and 959 cfs, respectively. The peak outflow discharges for the PMF and one-half of the PMF are 1,711 and 781 cfs, respectively. Since the spillway culvert is almost completely obstructed, its capacity has a negligible affect on the flood routings. The PMF overtopped the dam by 1.71 feet and one-half of the PMF overtopped the dam by 1.22 feet. The total duration of flow over the dam is 17.1 hours during the occurrence of the PMF and 15.0 hours during one-half of the PMF. The reservoir of Branneky Lake Dam is capable of storing a flood equal to approximately 5 percent of the PMF just before overtopping the dam. The reservoir of Branneky Lake Dam will not accommodate the one-percent chance flood nor the ten-percent chance flood without overtopping the dam. The one-percent chance flood will overtop the dam by 0.53 feet with a total duration of 12.9 hours and the ten-percent chance flood will overtop the dam by 0.15 feet with a total duration of 12.4 hours.

The surface soils on the embankment range from a clayey silt to a silty clay. The top of dam does have a good grass cover; however, the dam will be overtopped by 1.22 feet during the occurrence of the one-half PMF. The high velocity of flow across the top of the dam and on its downstream slope can cause severe erosion to the embankment and could lead to an eventual failure of the dam. The 46-foot wide crest of the dam, which has a good grass cover, may withstand some overtopping for a short period; however, due to the long duration of overflow during the one-half PMF, the safety of the dam is definitely threatened.

The failure of the dam could cause extensive damage to the property downstream of the dam and possible loss of life. The estimated damage zone extends approximately one mile downstream of the dam and includes four dwellings, one building, and an interstate highway.

## SECTION 6: STRUCTURAL STABILITY

### 6.1 Evaluation of Structural Stability

#### a. Visual Observations

There were no major signs of settlement or distress observed on the embankment or foundation during the visual inspection. The source of standing water observed at the toe of the dam is unknown; however, if it is due to seepage, the condition could be detrimental to the stability of the dam. At the present time, the possible seepage does not appear to be serious enough to constitute an unsafe condition. The wave erosion on the upstream slope does not appear to endanger the structural integrity of the dam; however, continual erosion can only be detrimental to the stability of the embankment. In the absence of seepage and stability analyses, no quantitative evaluation of the structural stability can be made.

The structural stability of the spillway is good, however, it is so clogged with silt, heavy grass, and trees that it is severely hampered in carrying out its intended purpose.

#### b. Design and Construction Data

No design computations pertaining to the embankment were uncovered during the report preparation phase. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available. No embankment or foundation soil parameters were available for carrying out a conventional stability analysis on the embankment. No construction data or specifications relating to the degree of embankment compaction were available for use in a stability analysis.

c. Operating Records

No operating records are available relating to the stability of the dam or its appurtenant structures. No regulated outlet works were provided for the dam. The water level on the day of the visual inspection was 4.6 feet below the minimum top of dam.

d. Post Construction Changes

No post construction changes are known to exist which will affect the structural stability of the dam.

e. Seismic Stability

The dam is located in Seismic Zone 2, as defined in the "Recommended Guidelines for Safety Inspection of Dams" as prepared by the Corps of Engineers (see Plate 8). Seismic Zone 2 is characterized by a moderate earthquake hazard. An earthquake of the magnitude that would be expected in Seismic Zone 2 should not cause significant distress to a well designed and constructed earth dam. Available literature indicates that no active faults exist near the vicinity of the damsite. The maximum recorded historic magnitude earthquake in the immediate vicinity of the damsite was the January 24, 1902 event of magnitude 5 located at a distance of 12 miles southeast of the damsite. This event cannot be correlated with known tectonic structure and is considered to probably be related to the release of accumulated residual strain along a buried pre-Quaternary fault. The attenuation of this event to the damsite would produce a peak ground acceleration of less than 0.05g which would not produce a significant seismic impact on the dam.

## SECTION 7: ASSESSMENT/REMEDIAL MEASURES

### 7.1 Dam Assessment

The assessment of the general condition of the dam is based upon available data and the visual inspection. Detailed investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation, however, the investigation is intended to identify any need for such studies.

It should be realized that the reported condition of the dam is based upon observations of field conditions at the time of inspection along with data available to the inspection team.

It is also important to realize that the condition of a dam depends upon numerous and constantly changing internal and external factors, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be assurance that an unsafe condition could be detected.

#### a. Safety

The spillway capacity of Branneky Lake Dam is found to be unusually small and seriously inadequate. The reservoir will store about 5 percent of the PMF without overtopping the dam. If the dam is overtopped, the safety of the embankment will be in jeopardy. Due to the susceptibility of the material used for the embankment to erosion, high velocity flow on the downstream slope could cause excessive erosion and eventually lead to the failure of the dam.

The overall condition of the dam appears to be fair; however, the severe capacity reduction of the spillway due to the siltation in the corrugated metal pipe jeopardizes the safety of the dam. No quantitative evaluation of the structural safety of the embankment can be made in view of the absence of seepage and stability analyses. The present embankment, however, has performed satisfactorily since its construction without failure or evidence of instability. No evidence was observed to indicate that the dam has ever been overtopped. The safety of the dam can be improved if the deficiencies described in Sections 3.2 and 6.1a are properly corrected as described in Section 7.2b.

b. Adequacy of Information

The conclusions presented in this report are based upon field measurements, past performance and the present condition of the dam. Information on the design hydrology, hydraulic design, operation, and maintenance of the dam was not available. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.

c. Urgency

The remedial measures recommended in Paragraph 7.2b should be accomplished within a reasonable period of time. The items recommended in paragraph 7.2a should be pursued on a high priority basis.

d. Necessity for Phase II ~~Inspection~~

Based upon results of the Phase I inspection, assuming the remedial measures recommended in Paragraph 7.2 are undertaken, a Phase II inspection is not felt to be necessary.



## 7.2 Remedial Measures

### a. Alternatives

There are several general options that may be considered to reduce the possibility of dam failure or to diminish the harmful aspects of such a failure. Some of these options are:

1. Increase the spillway capacity to pass one-half of the PMF without overtopping the dam. The spillway should also be protected to prevent excessive erosion during the occurrence of one-half of the PMF.
2. Increase the height of the dam enough to pass one-half of the PMF without overtopping the dam; an investigation should be done which also includes studying the effects that increasing the height of the dam would have on the structural stability of the existing embankment. The overtopping depth during the occurrence of one-half of the PMF, stated in Section 5.1d, is not the required or recommended increase in the height of the dam.
3. A combination of 1 and 2 above.


### b. O & M Procedures

1. The spillway pipe should be cleared of sediment. The invert of the approach and discharge channels should be graded to reduce siltation in the pipe.
2. The area of standing water at the toe of the dam should be further investigated to determine if the condition is due to seepage or surface runoff. If the condition is indeed due to seepage, the area should be monitored to detect any changes in location, turbidity, and quantity of water. Any changes should be investigated further and repairs made as necessary.

3. The welded wire screen should be either enlarged and the vertical supports kept out of the channel bottom and side slope area or removed altogether.
4. All of the trees on the upstream slope and in the spillway channels should be removed and regrowth prevented. Removal of the trees should be under the guidance of an engineer experienced in the design and construction of earth dams.
5. All burrowing animals should be eliminated from the embankment and their burrows properly backfilled and compacted.
6. The erosion due to wave action on the upstream slope should be properly repaired and the slope adequately protected from further damage.
7. The vegetation on the embankment, especially the vegetation on the downstream slope, should be properly maintained and an adequate vegetative cover retained on the embankment to protect it from surface erosion and to prevent excessive erosion in the event the dam is overtopped. Large vegetation, such as bushes and trees, should be prevented from growing on the embankment.
8. Seepage and stability analyses should be performed by a professional engineer experienced in the design and construction of earth dams.
9. The owner should initiate the following programs:
  - (a) Periodic inspection of the dam by a professional engineer experienced in the design and construction of earth dams.


(b) Set up a maintenance schedule and log all visits to the dam for operation, repairs and maintenance.

PLATES




LOCATION MAP - BRANNEKY LAKE DAM

MO - 31393





SCALE 1:24,000




CONTOUR INTERVAL 10 FEET  
NATIONAL GEODETIC VERTICAL DATUM OF 1929

BRANNEKY LAKE DAM (MO.-31393)

DRAINAGE BASIN AND  
DOWNSTREAM HAZARD ZONE




BRANNEKY LAKE DAM (MO. 31393)  
PLAN AND ELEVATION  
(SHEET 1 OF 2)



SCALE:  
HORIZ. 1" = 50'  
VERT. 1" = 5'

SECTION A-A  
(SPILLWAY PROFILE)




SCALE:  
HORIZ. 1" = 50'  
VERT. 1" = 10'

MAXIMUM SECTION  
(STATION 1+40)

BRANNEKY LAKE DAM (MO. 31393)  
SPILLWAY PROFILE AND MAXIMUM SECTION  
(SHEET 2 OF 2)





⊕ LOCATION OF DAM

NOTE: LEGEND FOR THIS MAP IS ON PLATES 6 AND 7.

REFERENCE:



GEOLOGIC MAP OF MISSOURI  
DEPARTMENT OF NATURAL RESOURCES  
MISSOURI GEOLOGICAL SURVEY  
KENNETH H. ANDERSON, 1979


REGIONAL GEOLOGICAL MAP  
OF  
BRANNEKY LAKE DAM

LEGEND

<u>PERIOD</u>	<u>SYMBOL</u>	<u>DESCRIPTION</u>
QUATERNARY	Qal	ALLUVIUM: SAND, SILT, GRAVEL
PENNSYLVANIAN	Pp	PLEASANTON GROUP: CYCLIC DEPOSITS OF SANDSTONE, SHALE AND LIMESTONE
	Pm	MARMATON GROUP: CYCLIC DEPOSITS OF SHALE, LIMESTONE AND SANDSTONE
	Pcc	CHEROKEE GROUP: CYCLIC DEPOSITS OF SHALE, LIMESTONE AND SANDSTONE
MISSISSIPPIAN	Mm	ST. LOUIS FORMATION: LIMESTONE INTERBEDDED WITH SHALE
	Mm	SALEM FORMATION: LIMESTONE INTERBEDDED WITH SHALE
	Mm	WARSAW FORMATION: ARGILLACEOUS LIMESTONE AND CALCAREOUS SHALE
	Mo	KEOKUK-BURLINGTON FORMATION: CHERTY GRAYISH BROWN SANDY LIMESTONE
	Mk	UNDIFFERENTIATED CHOUTEAU GROUP: LIMESTONE
	Mk	HANNIBAL FORMATION: SHALE AND SILTSTONE

LEGEND

<u>PERIOD</u>	<u>SYMBOL</u>	<u>DESCRIPTION</u>
ORDOVICIAN	Ou	NOIX LIMESTONE
	Om <sub>k</sub>	MAQUOKETA SHALE, KIMMSWICK LIMESTONE
	Od <sub>p</sub>	DECORAH FORMATION: GREEN TO GRAY CALCAREOUS SHALE WITH THIN FOSSILIFEROUS LIMESTONE
	Os <sub>p</sub>	ST. PETER SANDSTONE
	Os <sub>pe</sub>	ST. PETER SANDSTONE, EVERTON FORMATION
	Oj <sub>d</sub>	JOACHIM DOLOMITE
	Oj <sub>c</sub>	JEFFERSON CITY DOLOMITE
		NORMAL FAULT
		INFERRED FAULT
	U =	UPTHROWN SIDE
	D =	DOWNTROWN SIDE



APPENDIX A

PHOTOGRAPHS TAKEN DURING INSPECTION




PHOTO INDEX  
FOR  
BRANNEY LAKE DAM



Photo 1 - View of the upstream slope from the right abutment.




Photo 2 - View of the top of dam from the right abutment with the spillway in the foreground.

Brannock Lake Dam



Photo 3 - View of the downstream slope from the right abutment. The area of standing water and trees at the toe of the dam is shown in the right-hand side of the Photo.



Photo 4 - Close-up view of the upstream showing the near vertical slope due to wave action. Note the evidence of the normal water surface level at the left-hand side of Photo.



Branneky Lake Dam



Photo 5 - View of the entrance to the approach channel of the spillway from the reservoir.



Photo 6 - View of the approach channel of the spillway. Note the partially plugged C.M.P. in the center of the Photo.

Brannoky Lake Dam



Photo 7 - Close-up view of the partially plugged 24-inch-diameter C.M.P. of the spillway.



Photo 8 - View of the discharge channel of the spillway looking towards the reservoir.

Branneky Lake Dam



Photo 9 - View of the discharge channel of the spillway looking downstream.




Photo 10 - View of the reservoir and rim.

Brannock Lake Dam



Photo 11 - View of an Interstate highway (I-70) and the Boise Cascade Building just downstream of the dam. Note the embankment in the background.



Photo 12 - View of two dwellings downstream of the dam, which appear to be in the downstream hazard zone. Note downstream channel in the foreground.

APPENDIX B

HYDROLOGIC AND HYDRAULIC COMPUTATIONS

## BRANNEKY LAKE DAM

### HYDROLOGIC AND HYDRAULIC DATA, ASSUMPTIONS AND METHODOLOGY

1. SCS Unit Hydrograph procedures and the HEC-1DB computer program are used to develop the inflow hydrographs. The hydrologic inputs are as follows:
  - (a) Twenty-four hours probable maximum precipitation from Hydro-meteorological Report No. 33, 24-hour 100-year rainfall and 24-hour 10-year rainfall of St. Louis, Missouri.
  - (b) Drainage area = 0.14 square miles.
  - (c) Lag time = 0.10 hours.
  - (d) Hydrologic Soil Group:  
Soil Group "C".
  - (e) Runoff curve number:  
CN = 78 for AMC II and CN = 90 for AMC III.
2. Flow rates over the dam are based on HEC-2 generated profiles assuming critical depth at the downstream edge of the top of the dam and Manning's  $n = 0.03$ . Flow over the spillway section are determined by assuming critical flow.
3. Floods are routed through Branneky Lake to determine the ability of the reservoir to store the inflow flood volume and the severity of overtopping of the dam.

ECI-4 PRC ENGINEERING CONSULTANTS, INC.

DAM SAFETY INSPECTION / MISSOURI SHEET NO. \_\_\_\_\_ OF \_\_\_\_\_  
 DAM NAME: Branney Lake Dam (MO 31393) JOB NO. 1283  
 UNIT HYDROGRAPH PARAMETERS BY JFK DATE 3/12/81

- 1) DRAINAGE AREA,  $A = 0.14 \text{ sq. mi.} = (89.5 \text{ acres})$
- 2) LENGTH OF STREAM,  $L = (1.1'' \times 2000' = 2,200') = 0.42 \text{ mi.}$
- 3) ELEVATION AT DRAINAGE DIVIDE ALONG THE LONGEST STREAM,  
 $H_1 = 611$
- 4) ELEVATION OF RESERVOIR AT SPILLWAY CREST,  $H_2 = 506.5$
- 5) ELEVATION OF CHANNEL BED AT  $0.85L$ ,  $E_{85} = 600$
- 6) ELEVATION OF CHANNEL BED AT  $0.10L$ ,  $E_{10} = 510$
- 7) AVERAGE SLOPE OF THE CHANNEL,  $S_{AVG} = (E_{85} - E_{10}) / 0.75L = 90 / 650 = 5.5\%$
- 8) TIME OF CONCENTRATION:

A) BY KIRPICH'S EQUATION,

$$t_c = [(11.9 \times L^3) / (H_1 - H_2)]^{0.385} = [11.9 \times (0.42)^3 / (611 - 506.5)]^{0.385} = 0.16 \text{ hrs.}$$

B) BY VELOCITY ESTIMATE,

$$SLOPE = 5.5\% \Rightarrow \text{AVG. VELOCITY} = 4 \text{ fps}$$

$$t_c = L / V = 2,200' / 4.0 \text{ fps} \times \frac{3600 \text{ s}}{\text{hr}} = 0.15 \text{ hrs}$$

$$\text{USE } t_c = 0.16 \text{ hrs}$$

$$9) \text{ LAG TIME, } t_L = 0.6 t_c = 0.10 \text{ hrs}$$

$$10) \text{ UNIT DURATION, } D \leq t_L / 3 = 0.032 \text{ hrs} < 0.083 \text{ hrs}$$

$$\text{USE } D = 0.083$$

$$11) \text{ TIME TO PEAK, } T_p = D/2 + t_L = 0.083/2 + 0.10 = 0.14 \text{ hrs}$$

12) PEAK DISCHARGE,

$$q_p = (484 \times A) / T_p = (484 \times 0.14 \text{ mi}^2) / 0.14 \text{ hrs} = 484 \text{ cfs}$$

## PRC ENGINEERING CONSULTANTS, INC.

Dam Safety Inspection

SHEET NO. \_\_\_\_\_ OF \_\_\_\_\_

Branneky Lake Dam (Mo. 31393)JOB NO. 1283Reservoir Elevation - Area DataBY JFKDATE 3/12/8

Elevation (MSL) (ft.)	Reservoir Surface Area (acres)	Remarks
490	0	Estimated streambed U/S at dam
500	2.0	Measured on U.S.G.S. 7.5' Quad
505	5.5	Measured on U.S.G.S. 7.5' Quad (estimated elev. of water surface shown)
506.5	7.0	Invert of unobstructed portion of spillway - Interpolated
508	8.5	Top of Dam (assumed) - Interpolated
510	11.0	Measured on U.S.G.S. 7.5' Quad
520	18.5	Measured on U.S.G.S. 7.5' Quad



Dam Safety Inspection


SHEET NO. \_\_\_\_\_ OF \_\_\_\_\_

Branney Lake Dam (MO. 31393)

JOB NO. 1283

Discharge Through Partially Obstructed Culvert

BY VFK DATE 3/17/81



$$\text{slope} = 0.1' / 20' = 0.005$$

$$\text{Area of Opening} = R^2 \cos^{-1} \left( \frac{R-h}{R} \right) - (R-h) \sqrt{2Rh-h^2} \quad \text{where } R = \text{radius of circle}$$

h = rise of segment

$$= 1^2 \cos^{-1} \left( \frac{1-.4}{1} \right) - (1-.4) \sqrt{2(.4) - .4^2}$$

$$= 0.45 \text{ ft}^2$$

$$\text{Area of 24" CMP} = \pi r^2 = \pi (1')^2 = 3.14 \text{ ft}^2$$

$$\text{Wetted Perimeter} = S + l \quad \text{, where}$$

$$S = D \cos^{-1} \frac{d}{R} \quad \text{, where}$$

S = length of arc  
l = length of span  
D = diameter of pipe  
d = D - h

$$l = 2d \tan \frac{S}{2R}$$

$$S = 2 \cos^{-1} 0.6 = 1.85'$$

$$l = 2(.4) \tan \frac{1.85}{2} = 1.59'$$

$$S + l = 1.85' + 1.59' = 3.45'$$

Full Flow Conditions:

$$K_{entrance} = 0.5$$

$$K_{exit} = 1.0$$

$$K_{friction} = \frac{29.16 n^2 L}{R_h^{4/3}} = \frac{29.16 (.03)^2 (20)}{(1/3)^{4/3}} = 7.9$$

Dam Safety Inspection

SHEET NO. OF

Brannock Lake Dam (NIO. 31323)

JOB NO. 1283

Discharge Through Partially Obstructed Culvert

BY JFK

DATE 3/17/81

$$H = \frac{V^2}{2g}$$

$$H = \text{W.S.E.L.} - 506.5$$

$$V = \sqrt{\frac{2g}{C_d} H}$$

$$Q = VA$$

$$Q = \sqrt{\frac{2g}{C_d}} \cdot 15 \cdot (0.45)$$

$$Q = 1.5 \text{ cfs}$$

Storage at Top of Dam = 46 ac-ft

Storage at Spillway Invert = 34 ac-ft  
12 ac-ft storage

$$12 \text{ ac-ft} \times \frac{43560 \text{ ft}^2}{\text{ac}} \times \frac{1}{1.5 \text{ ft}^3} \times \frac{\text{hr}}{3600} \times \frac{\text{day}}{24 \text{ hr}} = 4 \text{ days}$$

Conclusion: The unobstructed portion of the culvert is sufficient to allow the water stored in the reservoir between the top of the dam and the culvert invert to drain within a four day period (approximately). Therefore, all routings can be started at elevation 506.5, but the discharge through the culvert can be neglected for the flood routings.

Sanitary Inspector


SHEET NO. OF

Bryn Mawr Lake Dam (No. 31323)

JOB NO. 1583-201

Overseer, Sanitary Inspector

BY J.F.K. DATE 2/13/91



Section 1: for  $0 \leq y_1 < 1.1$  for  $y_1 \leq 1.3$  for  $y_1 \geq 1.3$

$T = 200 + 76.9 y_1$   $T = 440$   
 $A = 11.200 + 10.2 y_1$   $A = 140.1$   
 NOTE: Assume ground water at 0.5 edge of crest, use HEC-2 to determine  $y_2$  at 1/2 edge crest

Section 2:  $Q = 509 H^{3/2}$   $H = W.S. EL. - 509.3$

Section 3: for  $y_2 < 2.0$  where  $V = \sqrt{A g / T}$

$y_1 = 4/5 H$   $y_2 = 2/3 (H + 0.5)$   
 $T = 7 y_2$   $T = 14$   
 $A = 14 (y_2 - 1)$   $Q = VA$

Refer to HE2-2 Diagram																	
Section #1				Section #2				W.S. EL.	H <sub>2</sub>	C	Q <sub>2</sub>	y <sub>2</sub>	T <sub>3</sub>	A <sub>3</sub>	V <sub>3</sub>	Q <sub>3</sub>	Q <sub>TOTAL</sub>
y <sub>1</sub>	T <sub>1</sub>	A <sub>1</sub>	V <sub>1</sub>	Q <sub>1</sub>	y <sub>1</sub>	T <sub>1</sub>	A <sub>1</sub>	V <sub>1</sub>									
0	0	0	0	0	0	0	0	0	508.0								0
.03	2.53	16.1	1.0	25	.22	24.3	50.6	.00	508.2								25
.1	2.49	24.9	1.3	50	.31	24.0	72.7	.01	508.3								50
.3	2.39	41.9	2.4	100	.43	238.6	106.0	.01	508.4								100
.50	2.20	58.4	2.9	200	.60	322.5	156.9	.03	508.6								200
.53	2.19	91.6	3.3	300	.72	347.7	238.1	.04	508.8								300
.70	2.03	123.0	3.8	400	.82	324.6	336.5	.04	508.9								400
.72	3.07	173.0	4.2	500	.92	397.9	470.5	.05	509.0								500
.73	3.38	243.7	4.5	750	1.11	425.1	646.3	.07	509.2	0	0	0	0	0	0	0	750
.79	3.62	323.0	4.9	1000	1.26	436.1	877.9	.09	509.4	0	0	0	0	0	0	0	1000
1.00	4.05	504.0	4.9	1500	1.50	440.0	1232.5	.13	509.6	2.92	5.5	.08	.56	.02	.11	.11	1500
1.13	4.30	676.7	5.3	2000	1.70	440.0	1640.0	.17	509.9	2.97	15.7	.16	.12	.09	.16	.16	2000
1.32	4.40	873.8	5.7	2500	1.87	440.0	2123.5	.21	510.1	2.99	23.0	.24	.168	.10	.20	.20	2500
1.45	4.40	976.9	6.0	3000	2.03	440.0	2530.0	.25	510.3	3.03	127.9	.64	4.48	1.43	3.2	4.6	3000
1.63	4.40	1093.5	6.7	4000	2.32	440.0	3379.2	.32	510.6	3.03	178.8	.80	5.60	2.24	3.6	8.1	4000
										3.04	245.9	.94	7.78	3.79	4.1	55	4281

HEC-2 INPUT AND SUMMARY TABLE

31/05/15. 15.02.97.

PAGE 1

.....  
HEL2 RELEASE DATED NOV 76 UPDATED APR 1990  
ERROR CORR - 0190200300  
MODIFICATION - 5051020500  
.....

01 MISSOURI DAM SAFETY  
02 OVERTOP RATING CURVE  
03 GRANNERY LAKE DAM

01	TOUCH	IND	MINV	INDM	SIRT	METRIC	HYING	9	WSEL	FO
-1.	2.	0.	0.	-1.000000	0.00	0.0	0.0	0.	509.000	0.000
1.000	0.000	-1.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000

05 VARIABLE CODES FOR SUMMARY PRINTOUT

SP	000	0.000	25.000	4.000	26.000	10.000	43.000	5.000	5.000	17.000
----	-----	-------	--------	-------	--------	--------	--------	-------	-------	--------

05 LPRINT NUMSEC \*\*\*\*\*REQUESTED SECTION NUMBERS\*\*\*\*\*

00	-10.000	-10.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
01	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
02	14.000	25.000	50.000	100.000	200.000	300.000	400.000	500.000	750.000	1000.000
03	1500.000	2000.000	2500.000	3000.000	4000.000	5000.000	6000.000	7000.000	8000.000	9000.000

04	1.000	2.000	3.000	4.000	5.000	6.000	7.000	8.000	9.000	10.000
05	511.000	0.000	509.100	0.000	508.000	190.000	508.000	509.300	509.000	440.000
06	511.000	440.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000

07	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
08	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000

.....  
 DECP RELEASE DATED NOV 76 UPDATED APRIL 1980  
 ERPGM CORR - 31.02.03.04  
 MODIFICATION - 30.01.00.53.04  
 .....

NOTE- ASTERISK (\*) AT LEFT OF CROSS-SECTION NUMBER INDICATES MESSAGE IN SUMMARY OF ERRORS LIST

BRANNIKY LAKE DAM

SUMMARY PRINTOUT

SECTNO	DEPTH	AREA	TOPWID	VCH	HV	U	FG	10K+S	K+RNCH
1.000	.14	16.06	215.77	1.56	.04	21.00	508.11	315.71	30.00
1.000	.12	25.50	224.90	1.93	.06	50.00	508.18	271.05	30.00
1.000	.19	41.06	238.95	2.39	.09	100.00	508.28	237.29	30.00
1.000	.30	68.41	260.65	2.92	.13	200.00	508.43	207.36	30.00
1.000	.38	91.58	278.21	3.28	.17	300.00	508.55	192.43	30.00
1.000	.46	112.92	293.45	3.54	.19	400.00	508.65	182.76	30.00
1.000	.52	133.02	307.13	3.76	.22	500.00	508.74	175.72	30.00
1.000	.67	179.89	336.85	4.17	.27	750.00	508.94	163.52	30.00
1.000	.79	223.00	362.04	4.40	.31	1000.00	509.11	156.40	30.00
1.000	1.00	303.98	405.14	4.93	.38	1500.00	509.38	149.57	30.00
1.000	1.18	376.72	430.58	5.31	.44	2000.00	509.62	137.32	30.00
1.000	1.32	437.80	440.00	5.71	.51	2500.00	509.82	133.90	30.00
1.000	1.45	496.09	440.00	6.04	.57	3000.00	510.02	126.53	30.00
1.000	1.69	599.47	440.00	6.67	.69	4000.00	510.38	120.50	30.00
2.000	.22	50.55	246.26	.49	.00	21.00	508.23	8.23	30.00
2.000	.31	72.71	264.00	.69	.01	50.00	508.32	10.76	30.00
2.000	.43	105.99	280.59	.94	.01	100.00	508.44	13.80	30.00
2.000	.60	150.79	322.54	1.28	.03	200.00	508.62	17.35	30.00
2.000	.72	198.11	347.71	1.51	.04	300.00	508.76	19.79	30.00
2.000	.92	235.47	369.56	1.69	.04	400.00	508.87	21.15	30.00
2.000	.93	260.98	387.64	1.85	.05	500.00	508.97	22.64	30.00
2.000	1.11	346.29	425.11	2.17	.07	750.00	509.18	25.13	30.00
2.000	1.26	407.92	456.12	2.45	.09	1000.00	509.35	26.79	30.00
2.000	1.50	511.43	490.00	3.00	.13	1500.00	509.63	27.82	30.00
2.000	1.70	604.57	440.00	3.81	.17	2000.00	509.87	29.29	30.00
2.000	1.87	682.25	440.00	4.66	.21	2500.00	510.04	30.62	30.00
2.000	2.03	752.96	440.00	5.98	.25	3000.00	510.28	31.77	30.00
2.000	2.22	879.18	440.00	6.55	.32	4000.00	510.44	32.75	30.00

1703/15. 15. 0.45.

SUMMARY OF FINDINGS

CAUTION	SEC003	1.000	PROFILE=1	CRITICAL DEPTH ASSURED
CAUTION	SEC007	1.000	PROFILE=2	CRITICAL DEPTH ASSURED
CAUTION	SEC010	1.000	PROFILE=3	CRITICAL DEPTH ASSURED
CAUTION	SEC013	1.000	PROFILE=4	CRITICAL DEPTH ASSURED
CAUTION	SEC016	1.000	PROFILE=5	CRITICAL DEPTH ASSURED
CAUTION	SEC019	1.000	PROFILE=6	CRITICAL DEPTH ASSURED
CAUTION	SEC022	1.000	PROFILE=7	CRITICAL DEPTH ASSURED
CAUTION	SEC025	1.000	PROFILE=8	CRITICAL DEPTH ASSURED
CAUTION	SEC028	1.000	PROFILE=9	CRITICAL DEPTH ASSURED
CAUTION	SEC031	1.000	PROFILE=10	CRITICAL DEPTH ASSURED
CAUTION	SEC034	1.000	PROFILE=11	CRITICAL DEPTH ASSURED
CAUTION	SEC037	1.000	PROFILE=12	CRITICAL DEPTH ASSURED
CAUTION	SEC040	1.000	PROFILE=13	CRITICAL DEPTH ASSURED
CAUTION	SEC043	1.000	PROFILE=14	CRITICAL DEPTH ASSURED

SUMMARY OF PMF AND ONE-HALF PMF ROUTING





# SUMMARY OF DAM SAFETY ANALYSIS

1 .....	ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM		TIME OF		TIME OF	
	RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	MAX OUTFLOW HOURS	FAILURE HOURS				
	.50	509.22	1.22	57.	781.	15.00	15.75	0.00				
	1.00	509.71	1.71	62.	1711.	17.08	15.67	0.00				

PERCENT OF PMF ROUTING  
EQUAL TO SPILLWAY CAPACITY

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 11 APR 77  
 \*\*\*\*\*

1	A1	MISSOURI DAM SAFETY									
2	A2	BRANNICKY LAKE DAM (MO.31253)									
3	A3	PERCENT PMF									
4	B	5	0	0	0	0	0	0	-4	0	
5	B1	5	1	1	1	1	1	1	1	0	
6	J	1	1	1	1	1	1	1	1	1	
7	J1	.05	.05	.05	.05	.05	.05	.05	.05	.05	
8	K	DA BRNKY									
9	K1	RUNOFF CALCULATION FOR BRANNICKY LAKE DRAINAGE AREA									
10	M	1	1	1	1	1	1	1	1	1	
11	P	1	1	1	1	1	1	1	1	1	
12	T	25.	100	120	130	130	130	130	130	130	
13	T2	.1	.1	.1	.1	.1	.1	.1	.1	.1	
14	X	1	1	1	1	1	1	1	1	1	
15	K	BRANNICKY DM									
16	K1	ROUTE HYDROGRAPH THROUGH BRANNICKY LAKE									
17	Y	1	1	1	1	1	1	1	1	1	
18	Y1	1	1	1	1	1	1	1	1	1	
19	Y4	503	503.2	508.3	508.4	508.6	508.8	508.9	509	509.4	
20	Y4	509.6	509.9	510.1	510.3	510.6	510.8	510.9	511	511.4	
21	Y5	0	25	50	100	200	300	400	500	500	
22	Y5	1516	2029	2633	3187	4281	500	500	500	500	
23	LA	0	2.0	5.5	7.0	8.5	11.0	18.5	18.5	18.5	
24	SE	490	500	505	506.5	508	510	520	520	520	
25	IS	505.5	505.5	505.5	505.5	505.5	505.5	505.5	505.5	505.5	
26	AD	508	508	508	508	508	508	508	508	508	
27	K	39	39	39	39	39	39	39	39	39	

# SUMMARY OF DAM SAFETY ANALYSIS

RATIO OF PPE	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
1 .....	ELEVATION STORAGE OUTFLOW	INITIAL VALUE	SPILLWAY CFFST	TIP OF DAM			
		505.50	506.50	504.00			
		34.	34.	46.			
		0.	0.	0.			
.05	507.98	0.00	45.	0.	0.00	0.00	0.00
.06	508.09	.09	46.	11.	8.08	18.08	0.00
.07	508.14	.14	47.	17.	9.08	17.50	0.00
.08	508.20	.20	47.	25.	9.33	17.00	0.00
.09	508.29	.29	48.	47.	6.42	16.00	0.00

SUMMARY OF ONE-PERCENT CHANCE FLOOD ROUTING

\*\*\*\*\*  
 FLOOD HYDROGRAPH PACKAGE (HEC-1)  
 DAM SAFETY VERSION JULY 1978  
 LAST MODIFICATION 01 APR 80  
 \*\*\*\*\*

1	A1	MISSOURI DAM SAFETY									
2	A2	BRANNEY LAKE DAM (MO.31393)									
3	A3	100-YEAR STORM (ST. LOUIS DISTRIBUTION)									
4	B	300	0	5	0	0	0	0	0	0	0
5	B1	5									
6	J	1	1								
7	J1	1									
8	K	DA BRNKY									
9	K1	RUNOFF CALCULATION FOR BRANNEY LAKE DRAINAGE AREA									
10	M	2	.14	.14	.14	.14	.14	.14	.14	.14	.14
11	O	288									
12	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
13	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
14	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
15	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
16	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
17	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
18	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
19	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
20	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
21	O1	.012	.012	.012	.012	.012	.012	.012	.012	.012	.012
22	O1	.012	.012	.012	.012	.012	.012	.012	.012	.012	.012
23	O1	.023	.023	.023	.023	.023	.023	.023	.023	.023	.023
24	O1	.023	.023	.023	.023	.023	.023	.023	.023	.023	.023
25	O1	.030	.030	.030	.030	.030	.030	.030	.030	.030	.030
26	O1	.134	.255	.546	.817	.380	.255	.134	.134	.134	.134
27	O1	.049	.049	.048	.048	.048	.048	.030	.030	.030	.030
28	O1	.030	.030	.023	.023	.023	.023	.023	.023	.023	.023
29	O1	.023	.023	.023	.023	.023	.023	.023	.023	.023	.023
30	O1	.012	.012	.012	.012	.012	.012	.012	.012	.012	.012
31	O1	.012	.012	.012	.012	.012	.012	.012	.012	.012	.012
32	O1	.012	.012	.012	.012	.012	.012	.012	.012	.012	.012
33	O1	.012	.012	.012	.012	.012	.012	.012	.012	.012	.012
34	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
35	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
36	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
37	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
38	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
39	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007
40	O1	.007	.007	.007	.007	.007	.007	.007	.007	.007	.007

B-18





## SUMMARY OF DAM SAFETY ANALYSIS

	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
ELEVATION	506.50	506.50	509.00
STORAGE	34.	34.	46.
OUTFLOW	0.	0.	0.

MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
508.53	.53	50.	166.	12.92	12.42	0.00
11.00						

B-20

SUMMARY OF TEN-PERCENT CHANCE FLOOD ROUTING



-1 -78

1

1

1BRNKY DM

ROUTE HYDROGRAPH THROUGH BRANNEY LAKE

1-

1

-506.5 -1-

509 509.2 509.4

[illegible]

0	50	100	200	300	400	500	750	1006
12								
13								
14								
15								
16								
17								
18								
19								
20								
21								
22								
23								
24								
25								
26								
27								
28								
29								
30								
31								
32								
33								
34								
35								
36								
37								
38								
39								
40								
41								
42								
43								
44								
45								
46								
47								
48								
49								
50								
51								
52								
53								
54								
55								
56								
57								
58								
59								
60								
61								
62								
63								
64								
65								
66								
67								
68								
69								
70								
71								
72								
73								
74								
75								
76								
77								
78								
79								
80								
81								
82								
83								
84								

51  
52  
53  
54  
55  
56

51  
52  
53  
54  
55  
56

51  
52  
53  
54  
55  
56

51  
52  
53  
54  
55  
56

51  
52  
53  
54  
55  
56

51  
52  
53  
54  
55  
56

51  
52  
53  
54  
55  
56

51  
52  
53  
54  
55  
56

51  
52  
53  
54  
55  
56

51  
52  
53  
54  
55  
56

51  
52  
53  
54  
55  
56

51  
52  
53  
54  
55  
56

# SUMMARY OF DAM SAFETY ANALYSIS

1 .....

ELEVATION		INITIAL VALUE	SPILLWAY CREST	TOP OF DAM			
STORAGE		506.50	506.50	508.00			
OUTFLOW		34.	34.	46.			
		0.	0.	0.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
1.00	508.15	.15	47.	19.	12.42	13.58	0.00

ATE  
ME